

Appendix A
Site Visit Photos

Photo 1 Site 1a. Looking downstream at the sinuous channel with bare banks with undercutting at station 1+50.



Photo 2: Site 1a. Looking downstream at station 2+75. The left bank is bare at a vertical angle, while the right bank is angled and has a soil material change at the bottom foot of the bank.



Photo 3: Site 1b. Looking downstream at sediment build up on left bank and bare right bank at station 4+60



Photo 4: Site 1b. Looking downstream at station 5+00, both banks have tree roots present.



Photo 5: Site 1c. Looking downstream at station 6+40, slight undercut for left bank and slumping on the right bank.



Photo 6: Site 1d. Looking downstream at the straight channel segment at station 7+20.



Photo 7: Site 1d. Looking downstream at station 7+75, the right bank is eroding due to a sharp turn and could encroach on the trail.



Photo 8: Site 1e. Looking downstream at station 9+25, the left bank is angled and bare while the right bank is vertical with spotty plant coverage.



Photo 9: Site 1f. The creek begins to become more sinuous at station 11+40 and the left bank has undercut.



Photo 10: Site 1f. Looking downstream at station 12+50, low bank on left side, higher bank on right side, plant cover is intermittent.



Photo 11: Site 1g. Looking downstream at station 14+00, both banks are low with some undercutting.



Photo 12: Site 1g. Looking downstream at station 15+10, multiple outlets enter this location and could contribute to the eroding banks.



Photo 13: Site 1h. Looking downstream at station 16+00, upstream of a large pool that is at least 6 feet deep.



Photo 14: Site 1h. Looking downstream at station 16+80, the channel becomes sinuous and sediment deposition has occurred on the right bank.



Photo 15: Site 2a. Looking downstream at station 19+20, this location is downstream of an outlet; flows with high exit velocities are eroding the left bank.



Photo 16: Site 2a. Looking downstream at station 20+30, the right bank is bare and vertical. There are two footbridges in this vicinity.



Photo 17: Site 2b. Looking downstream at station at 22+00, there is a buildup of sediment in the channel that is approximately 40 feet by 100 feet in area.



Photo 18: Site 2b. Looking upstream at 23+20. Roughly 40% of the channel width is filled in. Most of the sediment buildup is 1 foot above the water surface level, with a few locations reaching 2 feet higher than the water surface.



Photo 19: Site 2c. Looking downstream at station 23+50 from the pedestrian trail.



Photo 20: Site 2c. Looking downstream at station 24+80 with steep eroding banks and woody debris in the channel.



Photo 21: Site 2d. Looking upstream at station 26+50, both banks are angled at approximately 60 degrees and are bare.



Photo 22: Site 2d. Looking at the right bank at station 27+90, the bank is mostly exposed.



Photo 23: Site 2e. Looking downstream at station 30+30, the right bank is bare while the left bank had moderate cover.



Photo 24: Site 2e. Looking downstream at station 31+10, woody debris has fallen into the channel and there is slight sediment accumulation at the bottom of the banks.



Photo 25: Site 2f. Looking downstream at station 34+40, multiple fallen trees in the channel creating woody debris and potential channel blockages.



Photo 26: Site 3a. Looking downstream at the sediment island formed at station 37+00 due to the pipe crossing at Vicksburg Road. The island width ranges from 1 to 10 feet wide, is 30-feet long, and roughly 1 foot above the water surface level.



Photo 27: Site 3c. Looking downstream at station 42+90, both banks have minimal vegetative surface protection.



Photo 28: Site 3c. Looking downstream at a bend at station 45+20.



Photo 29: Site 3d. Looking downstream at station 46+70 where the channel widens.



Photo 30: Site 3d. Looking downstream at station 47+50, the channel has bare banks and minor meandering and good floodplain connection.



Photo 31: Site 4a. Looking downstream at station 54+00, downstream of the Rockford Road crossing. Undercut bank (six inches or less).



Photo 32: Site 4a. Looking downstream at station 55+00, both banks have slight undercutting at the water line.



Photo 33: Site 4b. Looking downstream at station 57+00, the banks are vertical and bare.



Photo 34: Site 4b. Looking downstream at station 57+80, woody debris has fallen into the channel.



Photo 35: Site 4c. Looking downstream at station 59+00, the right bank is undercut below the tree roots.



Photo 36: Site 4c. Looking downstream at station 60+00, the left bank is undercut.



Photo 37: Site 4d. Looking downstream at station 62+30, sediment accumulation on the right bank.



Photo 38: Site 4e. Looking downstream at station 63+00, mild channel blockage.



Photo 39: Site 4e. Looking downstream at station 64+20, upstream of a larger deep pool.



Photo 40: Site 4f. Looking downstream at station 65+60, the banks are bare but have good floodplain connection



Photo 41: Site 4f. Looking downstream at station 66+90 towards the 38th Avenue crossing. The center and right culvert are partially blocked by sediment deposition.



Photo 42: Site 4g. Looking upstream at station 69+00 towards the 38th Avenue crossing. Slight sediment build up in center of channel near the culverts.






Appendix B

Open House Materials

About the Bassett Creek Watershed Management Commission (BCWMC)

The vision: stewardship of water resources to protect and enhance our communities



Plymouth Creek Restoration (2026 CR-P)

About the BCWMC

- Regional government organization formed in 1969 to focus on flood control along Bassett Creek
- Operates under a 10-year management plan
- Focused on providing flood management and improving and protecting the water quality of Bassett Creek and lakes/streams
- **Nine member cities:** Crystal, Golden Valley, Medicine Lake, Minneapolis, Minnetonka, New Hope, Plymouth, Robbinsdale, St. Louis Park,
- **Area:** approximately 40 square miles



Commission funding

- Contributions from nine member cities (approximately \$600,000 per year)
- Hennepin County tax levy for major projects (approximately \$1.5–2 million per year)
- Grant funds and application fees (varies)

Commission activities

- Implements capital improvement projects that reduce flooding and improve lakes, streams, and wetlands throughout the watershed
- Monitors water quality, performs studies, maps resources
- Provides water resource education and watershed-wide coordination
- Reviews developments for compliance with standards and requirements

EXAMPLE BCWMC CIP PROJECTS



Wirth Lake outlet



Plymouth Creek restoration (before and after)

Plymouth Creek Restoration Project



Plymouth Creek Erosion Issues and Restoration Prioritization



Restoration Prioritization Factors

Several factors will impact prioritization of Plymouth Creek restoration locations, including:

- Severity of existing erosion
- Public access/ownership
- Protection of existing structures/infrastructure
- Impact to surrounding areas
- Public visibility/accessibility
- Potential for future erosion (near-bank stress and bank erosion hazard index ratings)
- Opportunity for habitat creation or restoration
- Maintaining healthy, native significant trees (minimize removal)
- Vegetation establishment potential (exposure to sunlight)
- Ease of construction access
- Consideration of proximity/possibility for other improvements (e.g. new sediment trapping device in nearby storm drains)
- Potential for public education/signage

Any type of erosion comes with the associated issues:


- Introduction of sediment to stream and downstream waterbodies
- Degradation of bank vegetation and reduced potential for re-growth
- Degradation of in-stream and bank habitats
- Increased risk of continued erosion
- Changed stream shape and size over time

Plymouth Creek Restoration Project




Stream Stabilization Methods

1




In-stream structures

2



Bank stabilization with bioengineering methods

3



Bank grading with riprap and vegetation establishment

Pros

- Reduces near-bank stress
- Minimal bank disturbance
- Lowest construction cost
- Diversifies flow within stream, including energy dissipation pools
- Provides in-stream habitat

- More erosion protection along the base of the bank, also known as the bank toe
- Bioengineering and vegetation features can improve in-stream and bank habitat

- Riprap allows for the most protection against damaging (high shear stress) flows
- Immediate stabilization of eroding areas

Cons

- In-stream features can be obstructed with sediment and debris
- Continued erosion on unprotected bank toe outside the zone of influence of the structures

- Requires establishment period for vegetation features
- Moderate grading can increase construction costs, bank disturbance, and potential tree removal



- Riprap provides minimal in-stream or bank habitat
- Riprap and grading are more cost intensive
- Most bank disturbance during construction, and potential tree removal

Potential Re-meandering


In 1947, Plymouth Creek was ditched and straightened, possibly to improve access to agricultural fields. It is likely that even the pre-1947 channel had been altered from the original stream flowpath. Natural channels are typically sinuous, and re-establishing a meandering pattern can be an important part of restoring a ditched and straightened stream. Creek re-meandering is one restoration option under consideration for the portion of the creek that is west and south of Plymouth Creek Elementary School.

Benefits of Re-meandering

- Increases stream length and sinuosity
- Decreases flow rates and likelihood of bank erosion
- Increases resiliency during higher flow storm events
- Enhances habitat
- Promotes groundwater connectivity
- Enhances geomorphic processes including sediment transport and deposition




Preliminary Concept for Reach 1, Dunkirk Lane to Yuma Lane




- Regrade channel and stream banks to improve floodplain connection and soften tight curves
- Stabilize stream bank toe with rock riprap, coconut-fiber (coir) log, or root wads
- Stabilize stream bank with vegetative material (seed, live plugs, shrubs, and/or live cuttings)
- Remove invasive buckthorn within riparian zone and replace with native plantings

● Significant Trees
~ Plymouth Creek
--- Bike and/or Pedestrian Trail
 Parcel Boundary
 Public Parcel
 Easements
Bank Erosion Hazard Index (BEHI)
--- Very High
--- High
--- Moderate
--- Low
Utilities
--- Gravity Storm Sewer
--- Sanitary Main
Bioengineering Features
--- Coir Log
--- Cross-Vanes
--- J-Hook
 Brush Mattresses
 Grading
 Live Staking
 Plug Planting
 Rock Riprap
 Seeding
 VRSS

* Significant tree: Any healthy tree measuring 8 inches in diameter or larger at a height of 54 inches above ground for deciduous trees, and measuring 4 inches in diameter or larger at a distance of 54 inches above ground for coniferous trees.



Preliminary Concept for Reach 2, Yuma Lane to Vicksburg Road



- Significant Trees
- ~ Plymouth Creek
- Bike and/or Pedestrian Trail
- Parcel Boundary
- Public Parcel
- ▨ Easements
- Bank Erosion Hazard Index (BEHI)**
- Very High
- High
- Moderate
- Low
- Utilities**
- Gravity Storm Sewer
- Sanitary Main
- Bioengineering Features**
- Coir Log
- Cross-Vanes
- J-Hook
- Root Wads
- Vanes
- ▨ Grading
- ▨ Plug Planting
- ▨ Rock Riprap
- ▨ Seeding
- ▨ VRSS

* Significant tree: Any healthy tree measuring 8 inches in diameter or larger at a height of 54 inches above ground for deciduous trees, and measuring 4 inches in diameter or larger at a distance of 54 inches above ground for coniferous trees.

0 100 200
Feet

- Regrade channel and stream banks to improve floodplain connection
- Install rock vanes to maintain channel grade and route erosive flows away from stream banks
- Stabilize stream bank with vegetative material (seed, live plugs, shrubs, and/or live cuttings)
- Remove invasive buckthorn within riparian zone and replace with native plantings


* See channel re-alignment board for potential stream meander layout next to school.

Preliminary Concept for Reach 3, Vicksburg Road to Rockford Road



- Significant Trees
- ~ Plymouth Creek
- - - Bike and/or Pedestrian Trail
- Parcel Boundary
- Public Parcel
- ▨ Easements
- Bank Erosion Hazard Index (BEHI)**
- Very High
- High
- Moderate
- Low
- Utilities**
- Gravity Storm Sewer
- Sanitary Main
- Bioengineering Features**
- Coir Log
- Cross-Vanes
- J-Hook
- Vanes
- Grading
- Live Staking
- Plug Planting
- Rock Riprap
- Seeding

* Significant tree: Any healthy tree measuring 8 inches in diameter or larger at a height of 54 inches above ground for deciduous trees, and measuring 4 inches in diameter or larger at a distance of 54 inches above ground for coniferous trees.



- Install rock vanes to maintain channel grade and J-hook vanes to route erosive flows away from stream banks
- Stabilize culvert outlets with grading, riprap, erosion control blanket, and/or live plugs and seed
- Remove invasive buckthorn within riparian zone and replace with native plantings


Preliminary Concept for Reach 4, Rockford Road to 38th Avenue



- Install rock vanes to maintain channel grade and J-hook vanes to route erosive flows away from stream banks
- Grade banks, place erosion control blanket and live plugs with live stakes and seeding to enhance floodplain
- Remove invasive buckthorn within riparian zone and replace with native plantings

● Significant Trees
~ Plymouth Creek
--- Bike and/or Pedestrian Trail
 Parcel Boundary
 Public Parcel
 Easements
Bank Erosion Hazard Index (BEHI)
--- Very High
--- High
--- Moderate
--- Low
Utilities
--- Gravity Storm Sewer
--- Sanitary Main
Bioengineering Features
--- Coir Log
--- Cross-Vanes
--- J-Hook
 Brush Mattresses
 Grading
 Live Staking
 Plug Planting
 Rock Riprap
 Seeding
 VRSS
 Debris Removal

* Significant tree: Any healthy tree measuring 8 inches in diameter or larger at a height of 54 inches above ground for deciduous trees, and measuring 4 inches in diameter or larger at a distance of 54 inches above ground for coniferous trees.



Timeline, Funding, and Project Impacts



Timeline (watch for project updates!)



[BCWMC Project Page](#)




Funding

BCWMC Capital Funds levied by Hennepin County on all watershed residents



Project Impacts

- Improve water quality
- Reduce erosion along creek
- Improve in-stream and riparian habitat
- Protect infrastructure and utilities along creek
- Limit trail closures
- Limit tree removals or replace, as warranted



Plymouth Creek Potential Riparian Vegetation Regeneration Overview



Plymouth Creek riparian areas have lost much of their ecological value and stormwater runoff treatment capacity due to changes within the watershed. Regenerating native vegetation within the riparian zone of Plymouth Creek provides many opportunities to meet District goals including:

- to restore ecological value
- to provide additional stormwater runoff treatment
- to clean up debris
- to restore wildlife habitat
- to provide passive recreation

Understory and herbaceous ground layer species within the riparian corridor vary from non-native invasives (e.g., Tatarian honeysuckle, common burdock, thistles, and buckthorn) to native generalists (e.g., snakeroot, woodbine, Canada goldenrod, and asters). This plant community structure and species composition is a direct result of past human disturbance (e.g., plowing, grading, grazing, etc.).

An invasive plant is defined as a plant that is non-native or native (e.g., Canada goldenrod, ragweed, and box elder) and has negative effects on our economy, environment, or human health. Invasive plants are aggressive species that can establish rapidly and outcompete native plants. When invasive species displace native plants they degrade wildlife habitat by altering the physical structural cover of a plant community and by eliminating essential food sources. Invasive species present along the creek, like buckthorn and garlic mustard, can create areas of exposed soils which lead to erosion and result in the degradation of water quality in lakes and streams. The removal of invasive species and the prevention of future species establishing is a project priority.



Existing Plant Community: **Plymouth Creek & Dunkirk Ln**




Existing Plant Community: **Plymouth Creek & Rockford Rd**



Existing Plant Community: **Plymouth Creek & 41st Ave**


Target Community



Example Target Plant Community: **Sedge Meadow**



Example Target Plant Community: **Sedge Meadow**



Example Target Plant Community: **Woodland**

Selective Clearing

Before re-introducing native plant communities, invasive and non-native perennial plants will be cleared. In addition, trees that are diseased, dying, and prone to infestation are to be identified for removal. Opening up the tree canopy allows for the reintroduction of the native plant communities that were once present. Trees targeted for tree removal include:

- Buckthorn
- Ash (emerald ash borer)
- Siberian elm
- Boxelder
- Dead or dying trees that may be a hazard



Plymouth Creek Riparian Area: **Existing Invasive Species**



Example of Tree Removal: **Forestry Mower Clearing Trees**



Example of Degraded Woodland Restoration: **Before**



Example of Degraded Woodland Restoration: **After**

How long will it take?

It can take 5-7 years for restored native plant communities to reach full maturity. Proper site maintenance following a planting is essential to reduce weed competition and ensure the success of the restoration project.

Year 1

The site will look bare and weedy during the first growing season. Cover crop grasses establish quickly (to stabilize soils) but native perennial plants may only grow to a height of six inches in a season. Mowing is the best way to control annual weeds during the first few years. Site mowing is typically done 2-3 times in the first year to prevent annual weeds from going to seed.



Example Woodland Restoration: **Year 1**

Year 2

Some of the short-lived flowering species bloom in abundance during the second year. Plants like wild bergamot, fragrant hyssop, and black-eyed Susan are usually the first to flower during restoration.

Mowing is generally limited to one or two times during the second year. Some herbicide spot spraying is anticipated for persistent woody invasive species.



Example Woodland Restoration: **Year 2**

Year 3 & Beyond

The composition and appearance of these planted communities will continue to fluctuate and evolve over time. Most native flowers and grasses begin to reach maturity during the third year.

The frequency of weed management activities will be reduced over time but continued management is going to be important for most restoration projects.



Example Woodland Restoration: **Year 3**



Appendix C

Restoration Table

Restoration Table

| Site Area Restoration | Severity of Existing Erosion ¹ | Creek Ownership | Riparian Ownership/Access for Stabilization ² | Riparian Ownership/Access for Vegetation Work ² | Ease of Construction Access ² | Protection of Existing Structures/ Infrastructure ² | Impact to Surrounding Areas ³ | Potential for Future Erosion (BEHI/NBS) ⁴ | Opportunity for Habitat Restoration (riparian/upland) Based on Proposes Stream Stabilization | Opportunity for Habitat Restoration (in channel) | Maintaining Healthy, Native Significant Trees ⁵ | Vegetation Establishment | Education Potential ⁶ | Count | Rank |
|--|---|-----------------|--|--|--|--|--|--|--|--|--|--------------------------|----------------------------------|-------|--------|
| 1a. Right and left bank stabilization with floodplain and channel realignment grading, rock toe, and vegetation establishment (Sta. 0+00 to 3+85) | 3 | 2 | 2 | 1 | 3 | 5 | 0 | 9 | 2 | 2 | 0 | 2 | 2 | 33 | High |
| 1b. Right and left bank stabilization with rock toe, plantings, and VRSS (Sta. 3+85 to 6+05) | 3 | 2 | 1 | 1 | 3 | 15 | 0 | 4 | 2 | 0 | 2 | 2 | 2 | 37 | High |
| 1c. Right bank stabilization with grading and plantings (Sta. 6+05 to 7+05) | 2 | 3 | 2 | 1 | 3 | 5 | 0 | 3 | 2 | 0 | 2 | 2 | 2 | 27 | Medium |
| 1d. Right bank stabilization with rock toe and VRSS (Sta. 7+05 to 8+90) | 1 | 3 | 3 | 1 | 0 | 5 | 0 | 2 | 2 | 0 | 2 | 2 | 2 | 23 | Medium |
| 1e. Right and left bank stabilization with rock toe, VRSS, plantings and cross vane (Sta. 9+10 to 10+20) | 2 | 3 | 2 | 1 | 0 | 5 | 0 | 3 | 2 | 2 | 2 | 2 | 2 | 26 | Medium |
| 1f. Right and left bank stabilization with coir logs, grading, and plantings (Sta. 10+20 to 13+55) | 3 | 3 | 2 | 1 | 0 | 5 | 0 | 7 | 2 | 0 | 0 | 2 | 2 | 27 | Medium |
| 1g. Right and left bank stabilization with channel realignment, cross vanes, and plantings (Sta. 13+55 to 15+35) | 3 | 3 | 2 | 3 | 3 | 15 | 0 | 9 | 2 | 2 | 2 | 2 | 2 | 48 | High |
| 1h. Right and left bank stabilization with rock toe, vegetation, and j-hooks (Sta. 15+35 to 18+30) | 3 | 2 | 2 | 2 | 3 | 0 | 0 | 4 | 2 | 2 | 0 | 2 | 0 | 22 | Medium |

Restoration Table

| Site Area Restoration | Severity of Existing Erosion ¹ | Creek Ownership | Riparian Ownership/Access for Stabilization ² | Riparian Ownership/Access for Vegetation Work ² | Ease of Construction Access ² | Protection of Existing Structures/ Infrastructure ² | Impact to Surrounding Areas ³ | Potential for Future Erosion (BEHI/NBS) ⁴ | Opportunity for Habitat Restoration (riparian/upland) Based on Proposes Stream Stabilization | Opportunity for Habitat Restoration (in channel) | Maintaining Healthy, Native Significant Trees ⁵ | Vegetation Establishment | Education Potential ⁶ | Count | Rank |
|--|---|-----------------|--|--|--|--|--|--|--|--|--|--------------------------|----------------------------------|-------|--------|
| 2a. Right and left bank stabilization with rock toe, cross vanes, j-hook, and vegetation establishment (Sta. 18+70 to 21+00) | 3 | 2 | 2 | 2 | 3 | 0 | 0 | 4 | 2 | 2 | 0 | 2 | 0 | 22 | Medium |
| 2b. Grading to improve channel definition and improve settling capacity of basin (Sta. 21+00 to 23+30) | 0 | 2 | 2 | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 2 | 0 | 0 | 9 | Low |
| 2c. Right and left bank stabilization with grading, rock toe, root wads, log vanes, and vegetation establishment (Sta. 23+40 to 25+40) | 3 | 3 | 3 | 3 | 3 | 15 | 0 | 4 | 2 | 2 | 0 | 2 | 1 | 41 | High |
| 2d. Right and left bank stabilization with grading, root wads, log vanes, woody debris removal, and vegetation establishment (Sta. 25+40 to 29+30) | 3 | 3 | 3 | 3 | 3 | 0 | 0 | 4 | 2 | 2 | 0 | 2 | 1 | 26 | Medium |
| 2e. Right and left bank stabilization with grading banks and side channels, log vanes, woody debris removal, and vegetation establishment (Sta. 29+30 to 33+90) | 2 | 1 | 1 | 1 | 3 | 0 | 0 | 8 | 2 | 2 | 0 | 2 | 1 | 23 | Medium |
| 2f. Right and left bank stabilization with grading, woody debris removal, log vanes, and vegetation establishment (Sta. 33+90 to 36+00) | 1 | 1 | 1 | 1 | 3 | 0 | 0 | 3 | 2 | 2 | 2 | 2 | 1 | 19 | Medium |

Restoration Table

| Site Area Restoration | Severity of Existing Erosion ¹ | Creek Ownership | Riparian Ownership/Access for Stabilization ² | Riparian Ownership/Access for Vegetation Work ² | Ease of Construction Access ² | Protection of Existing Structures/ Infrastructure ² | Impact to Surrounding Areas ³ | Potential for Future Erosion (BEHI/NBS) ⁴ | Opportunity for Habitat Restoration (riparian/upland) Based on Proposes Stream Stabilization | Opportunity for Habitat Restoration (in channel) | Maintaining Healthy, Native Significant Trees ⁵ | Vegetation Establishment | Education Potential ⁶ | Count | Rank |
|--|---|-----------------|--|--|--|--|--|--|--|--|--|--------------------------|----------------------------------|-------|--------|
| 3a. Grading to improve channel definition and remove accumulated sediment (Sta. 37+00 to 38+00) | 0 | 3 | 1 | 1 | 3 | 0 | 0 | 1 | 0 | 0 | 2 | 0 | 2 | 13 | Low |
| 3b. Right and left bank vegetation management (Sta. 38+00 to 42+30) | 0 | 3 | 3 | 1 | 3 | 0 | 1 | 0 | 0 | 0 | 0 | 2 | 2 | 15 | Low |
| 3c. Right and left bank stabilization with cross vanes, j-hooks, and woody debris removal (Sta. 42+30 to 46+40) | 2 | 3 | 2 | 1 | 3 | 15 | 1 | 3 | 0 | 2 | 2 | 0 | 0 | 34 | High |
| 3d. Right and left bank stabilization with log vanes, plantings, and installation of riprap (Sta. 46+40 to 49+00) | 2 | 3 | 1 | 1 | 3 | 0 | 0 | 3 | 0 | 2 | 2 | 2 | 0 | 19 | Medium |
| 3e. Right and left bank vegetation management (Sta.49+00 to 51+50) | 0 | 3 | 3 | 1 | 3 | 0 | 1 | 0 | 0 | 0 | 0 | 2 | 2 | 15 | Low |

Restoration Table

| Site Area Restoration | Severity of Existing Erosion ¹ | Creek Ownership | Riparian Ownership/Access for Stabilization ² | Riparian Ownership/Access for Vegetation Work ² | Ease of Construction Access ² | Protection of Existing Structures/ Infrastructure ² | Impact to Surrounding Areas ³ | Potential for Future Erosion (BEHI/NBS) ⁴ | Opportunity for Habitat Restoration (riparian/upland) Based on Proposes Stream Stabilization | Opportunity for Habitat Restoration (in channel) | Maintaining Healthy, Native Significant Trees ⁵ | Vegetation Establishment | Education Potential ⁶ | Count | Rank |
|--|---|-----------------|--|--|--|--|--|--|--|--|--|--------------------------|----------------------------------|-------|--------|
| 4a. Right and left bank stabilization with cross vanes, rock riffles, coir log, grading, and vegetation establishment (Sta. 53+00 to 56+75) | 2 | 1 | 1 | 1 | 3 | 15 | 0 | 3 | 2 | 2 | 0 | 2 | 2 | 34 | High |
| 4b. Right and left bank stabilization with j-hooks and live staking (Sta. 56+75 to 58+60) | 3 | 3 | 3 | 1 | 3 | 0 | 1 | 4 | 2 | 2 | 2 | 2 | 2 | 28 | Medium |
| 4c. Right and left bank stabilization with grading, rock toe, cross vanes, and plantings (Sta. 58+60 to 61+10) | 2 | 3 | 3 | 1 | 3 | 0 | 0 | 3 | 2 | 2 | 2 | 2 | 2 | 25 | Medium |
| 4d. Right and left bank stabilization with riprap banks and live staking (Sta. 61+10 to 62+85) | 3 | 3 | 3 | 1 | 3 | 0 | 0 | 4 | 2 | 0 | 2 | 2 | 2 | 25 | Medium |
| 4e. Right and left bank stabilization with coir log, j-hooks, cross vanes, and live staking (Sta. 62+85 to 65+00) | 3 | 3 | 3 | 1 | 3 | 0 | 0 | 4 | 2 | 2 | 2 | 2 | 0 | 25 | Medium |
| 4f. Right and left bank stabilization with cross vanes, j-hook, and grading (Sta. 65+00 to 67+70) | 3 | 3 | 3 | 3 | 3 | 0 | 0 | 4 | 0 | 2 | 0 | 0 | 0 | 21 | Medium |
| 4g. Right and left bank stabilization with cross vane and grading to remove accumulated sediment (Sta. 68+50 to 70+00) | 2 | 3 | 3 | 3 | 3 | 5 | 0 | 3 | 0 | 2 | 0 | 0 | 2 | 26 | Medium |

[1] Based on maximum BEHI score for the reach. Moderate=1, High=2, Very high= 3

[2] Given score of 15 if protects a sanitary sewer, 5 for other infrastructure

[3] Given score of 1 if little earth work

[4] Based on adding maximum BEHI and NBS. Moderate BEHI=1, High BEHI=2, Very high BEHI= 3, Very low NBS=1, Low NBS=2, Moderate NBS=3, High NBS= 4, Very high NBS=5, Extreme NBS=6

[5] Given score of 2 if maintaining trees that are not buckthorn, box elder, green ash, and siberian elm

[6] Given score 2 if stream restoration would be seen by the trail. Given score of 1 if the stream restoration is near Plymouth Elementary.



Appendix D

Erosion Rates

Left Bank Erosion Rates

| Reach | Restoration Area | Site Length | Length of Eroding Bank (ft) | Length of Eroding Bank Repaired if repaired) | Est. Avg. Bank Height (ft) | BEHI rating | NBS rating | Est. Erosion Rate (ft/yr) | Est. Erosion Rate (CF/yr) | Est. Sed. Load (ton/yr) | Est "Stable" Erosion Rate (ft/yr) | Est "Stable" Sed. Load Rate (ft/yr) | "Stable" Sed. Load (ton/yr) | Est. Sed. Load Reduction (ton/yr) | TSS Reduction (lb/yr) | TP Reduction (lb/yr) | Rank of Site |
|------------------------|------------------|-------------|-----------------------------|--|----------------------------|-------------|------------|---------------------------|---------------------------|-------------------------|-----------------------------------|-------------------------------------|-----------------------------|-----------------------------------|-----------------------|----------------------|--------------|
| Station 0+00 To 3+85 | 1a | 385 | 75 | 75 | 3.0 | Moderate | Very Low | 0.01 | 2.3 | 0.1 | 0.005 | 1.1 | 0.1 | 0.1 | 110 | 0.1 | High |
| Station 0+00 To 3+85 | 1a | 385 | 35 | 35 | 3.0 | Moderate | Extreme | 0.3 | 31.5 | 1.5 | 0.005 | 0.5 | 0.0 | 1.5 | 2,980 | 1.5 | High |
| Station 0+00 To 3+85 | 1a | 385 | 127 | 127 | 2.6 | High | Very Low | 0.08 | 25.9 | 1.2 | 0.005 | 1.6 | 0.1 | 1.2 | 2,340 | 1.2 | High |
| Station 0+00 To 3+85 | 1a | 385 | 35 | 35 | 2.6 | High | Extreme | 0.4 | 35.7 | 1.7 | 0.005 | 0.4 | 0.0 | 1.7 | 3,390 | 1.7 | High |
| Station 0+00 To 3+85 | 1a | 385 | 10 | 10 | 3.0 | Very High | Very Low | 0.3 | 8.8 | 0.4 | 0.005 | 0.1 | 0.0 | 0.4 | 830 | 0.4 | High |
| Station 3+85 To 6+05 | 1b | 220 | 48 | 27 | 3.3 | Moderate | Very Low | 0.01 | 1.6 | 0.1 | 0.005 | 0.4 | 0.1 | 0.0 | 40 | 0.0 | High |
| Station 3+85 To 6+05 | 1b | 220 | 113 | 108 | 3.0 | High | Very Low | 0.08 | 27.2 | 1.3 | 0.005 | 1.6 | 0.1 | 1.2 | 2,350 | 1.2 | High |
| Station 6+05 To 7+05 | 1c | 100 | 33 | 15 | 3.0 | Moderate | Very Low | 0.01 | 1.0 | 0.0 | 0.005 | 0.2 | 0.0 | 0.0 | 20 | 0.0 | Medium |
| Station 6+05 To 7+05 | 1c | 100 | 58 | 22 | 3.0 | High | Very Low | 0.08 | 13.9 | 0.7 | 0.005 | 0.3 | 0.4 | 0.2 | 470 | 0.2 | Medium |
| Station 9+10 To 10+20 | 1e | 110 | 48 | 18 | 2.8 | Moderate | Very Low | 0.01 | 1.3 | 0.1 | 0.005 | 0.2 | 0.1 | 0.0 | 20 | 0.0 | Medium |
| Station 10+20 To 13+55 | 1f | 335 | 65 | 29 | 4.0 | Moderate | Very Low | 0.01 | 2.6 | 0.1 | 0.005 | 0.6 | 0.1 | 0.0 | 60 | 0.0 | Medium |
| Station 10+20 To 13+55 | 1f | 335 | 170 | 130 | 3.2 | High | Very Low | 0.08 | 43.7 | 2.1 | 0.005 | 2.1 | 0.6 | 1.5 | 3,010 | 1.5 | Medium |
| Station 13+55 To 15+35 | 1g | 180 | 105 | 40 | 2.5 | Moderate | Very Low | 0.008 | 2.1 | 0.1 | 0.005 | 0.5 | 0.1 | 0.0 | 30 | 0.0 | High |
| Station 13+55 To 15+35 | 1g | 180 | 13 | 13 | 2.8 | Very High | Very Low | 0.3 | 10.7 | 0.5 | 0.005 | 0.2 | 0.0 | 0.5 | 1,020 | 0.5 | High |
| Station 13+55 To 15+35 | 1g | 180 | 20 | 20 | 2.8 | Very High | Extreme | 0.5 | 27.5 | 1.3 | 0.005 | 0.3 | 0.0 | 1.3 | 2,620 | 1.3 | High |
| Station 15+35 To 18+30 | 1h | 295 | 245 | 245 | 2.9 | High | Very Low | 0.08 | 55.9 | 2.7 | 0.005 | 3.5 | 0.2 | 2.5 | 5,050 | 2.5 | Medium |
| Station 15+35 To 18+30 | 1h | 295 | 10 | 10 | 3.0 | Very High | Very Low | 0.3 | 8.7 | 0.4 | 0.005 | 0.1 | 0.0 | 0.4 | 830 | 0.4 | Medium |
| Station 18+70 To 21+00 | 2a | 360* | 332 | 332 | 3.0 | High | Very Low | 0.08 | 79.7 | 3.8 | 0.005 | 5.0 | 0.2 | 3.6 | 7,190 | 3.6 | Medium |
| Station 18+70 To 21+00 | 2a | 360* | 48 | 48 | 4.0 | Very High | Very Low | 0.3 | 57.1 | 2.8 | 0.005 | 1.0 | 0.0 | 2.7 | 5,410 | 2.7 | Medium |
| Station 21+00 To 23+30 | 2b | 230 | 224 | 0 | 1.0 | High | Very Low | 0.08 | 17.9 | 0.9 | 0.005 | 0.0 | 0.9 | 0.0 | 0 | 0.0 | Low |
| Station 23+40 To 25+40 | 2c | 200 | 98 | 63 | 2.5 | High | Very Low | 0.08 | 19.6 | 0.9 | 0.005 | 0.8 | 0.4 | 0.6 | 1,140 | 0.6 | High |
| Station 23+40 To 25+40 | 2c | 200 | 116 | 116 | 3.5 | Very High | Very Low | 0.3 | 121.9 | 5.9 | 0.005 | 2.0 | 0.1 | 5.8 | 11,550 | 5.8 | High |
| Station 25+40 To 29+30 | 2d | 390 | 325 | 315 | 4.5 | Very High | Very Low | 0.3 | 438.7 | 21.1 | 0.005 | 7.1 | 1.0 | 20.1 | 40,260 | 20.1 | Medium |
| Station 29+30 To 33+90 | 2e | 460 | 132 | 12 | 3.0 | Moderate | Very Low | 0.01 | 4.0 | 0.2 | 0.005 | 0.2 | 0.2 | 0.0 | 20 | 0.0 | Medium |
| Station 29+30 To 33+90 | 2e | 460 | 140 | 140 | 3.2 | High | Very Low | 0.08 | 36.0 | 1.7 | 0.005 | 2.2 | 0.1 | 1.6 | 3,250 | 1.6 | Medium |
| Station 29+30 To 33+90 | 2e | 460 | 40 | 40 | 3.2 | High | Low | 0.11 | 14.1 | 0.7 | 0.005 | 0.6 | 0.0 | 0.6 | 1,290 | 0.6 | Medium |
| Station 29+30 To 33+90 | 2e | 460 | 30 | 30 | 3.2 | High | Extreme | 0.4 | 38.4 | 1.8 | 0.005 | 0.5 | 0.0 | 1.8 | 3,650 | 1.8 | Medium |
| Station 29+30 To 33+90 | 2e | 460 | 14 | 0 | 0.0 | Very High | Very Low | 0.3 | 0.0 | 0.0 | 0.005 | 0.0 | 0.0 | 0.0 | 0 | 0.0 | Medium |

Left Bank Erosion Rates

| Reach | Restoration Area | Site Length | Length of Eroding Bank (ft) | Length of Eroding Bank Repaired if repaired) | Est. Avg. Bank Height (ft) | BEHI rating | NBS rating | Est. Erosion Rate (ft/yr) | Est. Erosion Rate (CF/yr) | Est. Sed. Load (ton/yr) | Est "Stable" Erosion Rate (ft/yr) | Est "Stable" Sed. Load Rate (ft/yr) | "Stable" Sed. Load (ton/yr) | Est. Sed. Load Reduction (ton/yr) | TSS Reduction (lb/yr) | TP Reduction (lb/yr) | Rank of Site |
|------------------------|------------------|-------------|-----------------------------|--|----------------------------|-------------|------------|---------------------------|---------------------------|-------------------------|-----------------------------------|-------------------------------------|-----------------------------|-----------------------------------|-----------------------|----------------------|--------------|
| Station 33+90 To 36+00 | 2f | 210 | 156 | 106 | 3.0 | Moderate | Very Low | 0.01 | 4.7 | 0.2 | 0.005 | 1.6 | 0.1 | 0.1 | 150 | 0.1 | Medium |
| Station 42+30 To 46+40 | 3c | 410 | 293 | 243 | 2.4 | Moderate | Very Low | 0.01 | 7.1 | 0.3 | 0.005 | 2.9 | 0.2 | 0.1 | 280 | 0.1 | High |
| Station 42+30 To 46+40 | 3c | 410 | 156 | 81 | 2.2 | High | Very Low | 0.08 | 27.0 | 1.3 | 0.005 | 0.9 | 0.7 | 0.6 | 1,260 | 0.6 | High |
| Station 46+40 To 49+00 | 3d | 260 | 60 | 60 | 3.0 | Moderate | Very Low | 0.01 | 1.8 | 0.1 | 0.005 | 0.9 | 0.0 | 0.0 | 90 | 0.0 | Medium |
| Station 53+00 To 56+75 | 4a | 375 | 270 | 270 | 2.0 | Moderate | Very Low | 0.01 | 5.4 | 0.3 | 0.005 | 2.7 | 0.1 | 0.1 | 260 | 0.1 | High |
| Station 53+00 To 56+75 | 4a | 375 | 62 | 62 | 2.0 | High | Very Low | 0.08 | 10.0 | 0.5 | 0.005 | 0.6 | 0.0 | 0.5 | 900 | 0.5 | High |
| Station 56+75 To 58+75 | 4b | 200 | 61 | 61 | 1.7 | Moderate | Very Low | 0.01 | 1.0 | 0.1 | 0.005 | 0.5 | 0.0 | 0.0 | 50 | 0.0 | Medium |
| Station 56+75 To 58+75 | 4b | 200 | 122 | 122 | 2.3 | High | Very Low | 0.08 | 22.4 | 1.1 | 0.005 | 1.4 | 0.1 | 1.0 | 2,020 | 1.0 | Medium |
| Station 58+75 To 61+10 | 4c | 235 | 129 | 129 | 3.1 | Moderate | Very Low | 0.01 | 4.0 | 0.2 | 0.005 | 2.0 | 0.1 | 0.1 | 190 | 0.1 | Medium |
| Station 58+75 To 61+10 | 4c | 235 | 64 | 24 | 2.9 | High | Very Low | 0.08 | 14.9 | 0.7 | 0.005 | 0.4 | 0.5 | 0.3 | 510 | 0.3 | Medium |
| Station 61+10 To 62+85 | 4d | 175 | 55 | 55 | 3.5 | Moderate | Very Low | 0.01 | 1.9 | 0.1 | 0.005 | 1.0 | 0.0 | 0.0 | 90 | 0.0 | Medium |
| Station 61+10 To 62+85 | 4d | 175 | 87 | 67 | 4.8 | High | Very Low | 0.08 | 33.0 | 1.6 | 0.005 | 1.6 | 0.4 | 1.1 | 2290 | 1.1 | Medium |
| Station 62+85 To 65+00 | 4e | 215 | 193 | 148 | 2.6 | High | Very Low | 0.08 | 39.5 | 1.9 | 0.005 | 1.9 | 0.5 | 1.4 | 2740 | 1.4 | Medium |
| Station 62+85 To 65+00 | 4e | 215 | 27 | 27 | 2.5 | Very High | Very Low | 0.3 | 20.2 | 1.0 | 0.005 | 0.3 | 0.0 | 1.0 | 1910 | 1.0 | Medium |
| Station 65+00 To 67+70 | 4f | 270 | 123 | 83 | 1.8 | High | Very Low | 0.08 | 17.7 | 0.9 | 0.005 | 0.7 | 0.3 | 0.5 | 1080 | 0.5 | Medium |
| Station 65+00 To 67+70 | 4f | 270 | 95 | 95 | 2.1 | Very High | Very Low | 0.3 | 59.8 | 2.9 | 0.005 | 1.0 | 0.0 | 2.8 | 5660 | 2.8 | Medium |
| Station 68+50 To 70+00 | 4g | 410 | 71 | 71 | 2.5 | Moderate | Very Low | 0.01 | 1.8 | 0.1 | 0.005 | 0.9 | 0.0 | 0.0 | 80 | 0.0 | Medium |

*Includes channel that flows into Plymouth Creek

Right Bank Erosion Rates

| Reach | Restoration Area | Site Length | Length of Eroding Bank (ft) | Length of Eroding Bank Repaired if repaired) | Est. Avg. Bank Height (ft) | BEHI rating | NBS rating | Est. Erosion Rate (ft/yr) | Est. Erosion Rate (CF/yr) | Est. Sed. Load (ton/yr) | Est "Stable" Erosion Rate (ft/yr) | Est "Stable" Sed. Load Rate (ft/yr) | "Stable" Sed. Load (ton/yr) | Est. Sed. Load Reduction (ton/yr) | TSS Reduction (lb/yr) | TP Reduction (lb/yr) | Rank of Site |
|------------------------|------------------|-------------|-----------------------------|--|----------------------------|-------------|------------|---------------------------|---------------------------|-------------------------|-----------------------------------|-------------------------------------|-----------------------------|-----------------------------------|-----------------------|----------------------|--------------|
| Station 0+00 To 3+85 | 1a | 385 | 124 | 124 | 4.3 | High | Very Low | 0.08 | 42.2 | 2.0 | 0.005 | 2.6 | 0.1 | 1.9 | 3810 | 1.9 | High |
| Station 0+00 To 3+85 | 1a | 385 | 55 | 55 | 4.3 | High | Moderate | 0.16 | 37.4 | 1.8 | 0.005 | 1.2 | 0.1 | 1.7 | 3490 | 1.7 | High |
| Station 0+00 To 3+85 | 1a | 385 | 50 | 50 | 4.3 | High | Extreme | 0.4 | 85.0 | 4.1 | 0.005 | 1.1 | 0.1 | 4.0 | 8080 | 4.0 | High |
| Station 0+00 To 3+85 | 1a | 385 | 102 | 102 | 3.8 | Very High | Very Low | 0.3 | 116.8 | 5.6 | 0.005 | 1.9 | 0.1 | 5.5 | 11060 | 5.5 | High |
| Station 3+85 To 6+05 | 1b | 220 | 220 | 220 | 0.0 | Moderate | Very Low | 0.008 | 0.0 | 0.0 | 0.005 | 0.0 | 0.0 | 0.0 | 0 | 0.0 | High |
| Station 0+00 To 3+85 | 1a | 385 | 40 | 40 | 3.8 | Very High | Extreme | 0.75 | 114.5 | 5.5 | 0.005 | 0.8 | 0.0 | 5.5 | 10950 | 5.5 | High |
| Station 3+85 To 6+05 | 1b | 220 | 168 | 168 | 3.9 | High | Very Low | 0.08 | 52.0 | 2.5 | 0.005 | 3.3 | 0.2 | 2.3 | 4700 | 2.3 | High |
| Station 3+85 To 6+05 | 1b | 220 | 37 | 37 | 3.5 | Very High | Very Low | 0.3 | 38.4 | 1.9 | 0.005 | 0.6 | 0.0 | 1.8 | 3640 | 1.8 | High |
| Station 6+05 To 7+05 | 1c | 100 | 72 | 56 | 3.3 | High | Very Low | 0.08 | 18.8 | 0.9 | 0.005 | 0.9 | 0.2 | 0.7 | 1330 | 0.7 | Medium |
| Station 7+05 To 8+90 | 1d | 185 | 181 | 111 | 4.5 | Moderate | Very Low | 0.01 | 8.2 | 0.4 | 0.005 | 2.5 | 0.3 | 0.1 | 240 | 0.1 | Medium |
| Station 9+10 To 10+20 | 1e | 110 | 74 | 58 | 5.0 | High | Very Low | 0.08 | 29.6 | 1.4 | 0.005 | 1.5 | 0.4 | 1.0 | 2100 | 1.0 | Medium |
| Station 9+10 To 10+20 | 1e | 110 | 2 | 2 | 5.0 | Very High | Very Low | 0.3 | 2.7 | 0.1 | 0.005 | 0.0 | 0.0 | 0.1 | 250 | 0.1 | Medium |
| Station 10+20 To 13+55 | 1f | 335 | 280 | 254 | 3.0 | Very High | Very Low | 0.3 | 247.9 | 11.9 | 0.005 | 3.7 | 1.3 | 10.6 | 21290 | 10.6 | Medium |
| Station 10+20 To 13+55 | 1f | 335 | 40 | 40 | 3.0 | Very High | High | 0.5 | 59.1 | 2.8 | 0.005 | 0.6 | 0.0 | 2.8 | 5640 | 2.8 | Medium |
| Station 13+55 To 15+35 | 1g | 180 | 89 | 25 | 3.0 | High | Very Low | 0.08 | 21.4 | 1.0 | 0.005 | 0.4 | 0.8 | 0.3 | 540 | 0.3 | High |
| Station 13+55 To 15+35 | 1g | 180 | 60 | 60 | 3.0 | High | High | 0.2 | 36.0 | 1.7 | 0.005 | 0.9 | 0.0 | 1.7 | 3380 | 1.7 | High |
| Station 15+35 To 18+30 | 1h | 295 | 264 | 264 | 3.8 | High | Very Low | 0.08 | 80.9 | 3.9 | 0.005 | 5.1 | 0.2 | 3.7 | 7310 | 3.7 | Medium |
| Station 18+70 To 21+00 | 2a | 360* | 171 | 141 | 1.5 | High | Very Low | 0.08 | 20.5 | 1.0 | 0.005 | 1.1 | 0.2 | 0.8 | 1530 | 0.8 | Medium |
| Station 18+70 To 21+00 | 2a | 360* | 45 | 45 | 3.3 | Very High | Very Low | 0.3 | 44.2 | 2.1 | 0.005 | 0.7 | 0.0 | 2.1 | 4190 | 2.1 | Medium |
| Station 21+00 To 23+30 | 2b | 230 | 26 | 0 | 1.0 | High | Very Low | 0.08 | 2.1 | 0.1 | 0.005 | 0.0 | 0.1 | 0.0 | 0 | 0.0 | Low |
| Station 23+40 To 25+40 | 2c | 200 | 78 | 78 | 2.5 | High | Very Low | 0.08 | 15.7 | 0.8 | 0.005 | 1.0 | 0.0 | 0.7 | 1420 | 0.7 | High |
| Station 23+40 To 25+40 | 2c | 200 | 75 | 75 | 4.5 | Very High | Very Low | 0.3 | 100.8 | 4.9 | 0.005 | 1.7 | 0.1 | 4.8 | 9550 | 4.8 | High |
| Station 25+40 To 29+30 | 2d | 390 | 288 | 288 | 5.0 | High | Very Low | 0.08 | 115.3 | 5.6 | 0.005 | 7.2 | 0.3 | 5.2 | 10410 | 5.2 | Medium |
| Station 25+40 To 29+30 | 2d | 390 | 95 | 95 | 4.5 | Very High | Very Low | 0.3 | 127.8 | 6.2 | 0.005 | 2.1 | 0.1 | 6.1 | 12100 | 6.1 | Medium |
| Station 29+30 To 33+90 | 2e | 460 | 434 | 434 | 3.0 | High | Very Low | 0.08 | 104.1 | 5.0 | 0.005 | 6.5 | 0.3 | 4.7 | 9400 | 4.7 | Medium |
| Station 29+30 To 33+90 | 2e | 460 | 50 | 50 | 3.0 | High | High | 0.2 | 30.0 | 1.4 | 0.005 | 0.8 | 0.0 | 1.4 | 2820 | 1.4 | Medium |
| Station 33+90 To 36+00 | 2f | 210 | 103 | 73 | 5.5 | High | Very Low | 0.08 | 45.3 | 2.2 | 0.005 | 2.0 | 0.7 | 1.4 | 2900 | 1.4 | Medium |
| Station 42+30 To 46+40 | 3c | 410 | 248 | 198 | 2.6 | Moderate | Very Low | 0.01 | 6.3 | 0.3 | 0.005 | 2.5 | 0.2 | 0.1 | 240 | 0.1 | High |
| Station 42+30 To 46+40 | 3c | 410 | 187 | 112 | 2.3 | High | Very Low | 0.08 | 33.7 | 1.6 | 0.005 | 1.3 | 0.7 | 0.9 | 1820 | 0.9 | High |

Right Bank Erosion Rates

| Reach | Restoration Area | Site Length | Length of Eroding Bank (ft) | Length of Eroding Bank Repaired if repaired) | Est. Avg. Bank Height (ft) | BEHI rating | NBS rating | Est. Erosion Rate (ft/yr) | Est. Erosion Rate (CF/yr) | Est. Sed. Load (ton/yr) | Est "Stable" Erosion Rate (ft/yr) | Est "Stable" Sed. Load Rate (ft/yr) | "Stable" Sed. Load (ton/yr) | Est. Sed. Load Reduction (ton/yr) | TSS Reduction (lb/yr) | TP Reduction (lb/yr) | Rank of Site |
|------------------------|------------------|-------------|-----------------------------|--|----------------------------|-------------|------------|---------------------------|---------------------------|-------------------------|-----------------------------------|-------------------------------------|-----------------------------|-----------------------------------|-----------------------|----------------------|--------------|
| Station 46+40 To 49+00 | 3d | 260 | 65 | 65 | 2.5 | Moderate | Very Low | 0.01 | 1.6 | 0.1 | 0.005 | 0.8 | 0.0 | 0.0 | 80 | 0.0 | Medium |
| Station 46+40 To 49+00 | 3d | 260 | 89 | 89 | 3.0 | High | Very Low | 0.08 | 21.4 | 1.0 | 0.005 | 1.3 | 0.1 | 1.0 | 1940 | 1.0 | Medium |
| Station 53+00 To 56+75 | 4a | 375 | 289 | 289 | 1.8 | Moderate | Very Low | 0.01 | 5.1 | 0.2 | 0.005 | 2.5 | 0.1 | 0.1 | 240 | 0.1 | High |
| Station 53+00 To 56+75 | 4a | 375 | 60 | 60 | 2.0 | High | Very Low | 0.08 | 9.6 | 0.5 | 0.005 | 0.6 | 0.0 | 0.4 | 870 | 0.4 | High |
| Station 56+75 To 58+75 | 4b | 200 | 144 | 144 | 2.5 | High | Very Low | 0.08 | 28.7 | 1.4 | 0.005 | 1.8 | 0.1 | 1.3 | 2590 | 1.3 | Medium |
| Station 56+75 To 58+75 | 4b | 200 | 52 | 52 | 2.0 | Very High | Very Low | 0.3 | 30.9 | 1.5 | 0.005 | 0.5 | 0.0 | 1.5 | 2930 | 1.5 | Medium |
| Station 58+75 To 61+10 | 4c | 235 | 241 | 201 | 3.4 | High | Very Low | 0.08 | 66.4 | 3.2 | 0.005 | 3.5 | 0.7 | 2.5 | 5000 | 2.5 | Medium |
| Station 61+10 To 62+85 | 4d | 175 | 143 | 113 | 4.6 | High | Very Low | 0.08 | 52.5 | 2.5 | 0.005 | 2.6 | 0.7 | 1.9 | 3740 | 1.9 | Medium |
| Station 61+10 To 62+85 | 4d | 175 | 20 | 20 | 3.6 | Very High | Very Low | 0.3 | 21.2 | 1.0 | 0.005 | 0.4 | 0.0 | 1.0 | 2000 | 1.0 | Medium |
| Station 62+85 To 65+00 | 4e | 215 | 277 | 232 | 3.3 | High | Very Low | 0.08 | 73.0 | 3.5 | 0.005 | 3.8 | 0.8 | 2.8 | 5520 | 2.8 | Medium |
| Station 62+85 To 65+00 | 4e | 215 | 143 | 143 | 2.6 | Very High | Very Low | 0.3 | 109.8 | 5.3 | 0.005 | 1.8 | 0.1 | 5.2 | 10390 | 5.2 | Medium |
| Station 65+00 To 67+70 | 4f | 270 | 265 | 225 | 2.3 | High | Very Low | 0.08 | 48.1 | 2.3 | 0.005 | 2.6 | 0.5 | 1.8 | 3680 | 1.8 | Medium |
| Station 68+50 To 70+00 | 4g | 410 | 193 | 193 | 1.7 | High | Very Low | 0.08 | 26.3 | 1.3 | 0.005 | 1.6 | 0.1 | 1.2 | 2370 | 1.2 | Medium |
| Station 68+50 To 70+00 | 4g | 410 | 95 | 95 | 0 | Very High | Very Low | 0.3 | 0 | 0 | 0.005 | 0 | 0 | 0 | 0 | 0 | Medium |

*Includes channel that flows into Plymouth Creek



Appendix E

Tree Loss Summary

Tree Loss Summary

| Species | Healthy Trees Removed for High, Medium, and Low Priority Sites | Healthy Trees Removed for High and Medium Low Priority Sites | Healthy Trees Removed for High Priority Sites |
|-------------------|--|--|---|
| Apple | 1 | 1 | 0 |
| Green Ash | 32 | 28 | 16 |
| American Basswood | 3 | 3 | 2 |
| Paper Birch | 1 | 1 | 1 |
| Box Elder | 105 | 99 | 38 |
| Buckthorn | 13 | 13 | 2 |
| Cottonwood | 29 | 29 | 19 |
| American Elm | 15 | 15 | 3 |
| Hackberry | 1 | 0 | 0 |
| Norway Maple | 3 | 0 | 0 |
| Silver Maple | 4 | 4 | 4 |
| Bur Oak | 7 | 7 | 4 |
| Pin Oak | 2 | 2 | 2 |
| Red Oak | 1 | 1 | 1 |
| White Pine | 1 | 1 | 1 |
| Norway Spruce | 3 | 3 | 3 |
| White Spruce | 4 | 3 | 3 |
| Black Willow | 23 | 23 | 8 |
| | 248 | 233 | 107 |



Appendix F

Cost Estimates

Cost Estimates

Plymouth Creek - Alternative 1, High Sites

| Item Description | Unit | Estimated Quantity | Unit Price | Extension |
|--|-------|--------------------|------------|------------|
| Mobilization | LS | 1 | \$ 39,240 | \$ 39,300 |
| Control of Water | LS | 1 | \$ 20,000 | \$ 20,000 |
| Erosion Control | LS | 1 | \$ 16,770 | \$ 16,800 |
| Clearing and Grubbing | ACRE | 0.6 | \$ 21,500 | \$ 12,900 |
| Clear and Grub Woody Invasive Plant Removal (<=6" DBH tree) | ACRE | 3.4 | \$ 5,700 | \$ 19,400 |
| Clear and Grub Woody Invasive Plant Removal (>=6" DBH tree) | EACH | 5 | \$ 700 | \$ 3,500 |
| Herbaceous vegetation herbicide treatment | ACRE | 3.4 | \$ 1,000 | \$ 3,400 |
| Select Tree Removal (>6") | EACH | 121 | \$ 450 | \$ 54,500 |
| Debris Removal | EACH | 2 | \$ 1,450 | \$ 2,900 |
| Grading | SY | 2350 | \$ 3 | \$ 7,100 |
| Common Excavation | CY | 280 | \$ 16 | \$ 4,500 |
| Fieldstone Riprap | TONS | 390 | \$ 120 | \$ 46,800 |
| Clear and Salvage Trees and Install as Root Wad | EACH | 1 | \$ 700 | \$ 700 |
| Cross Vane | EACH | 11 | \$ 4,200 | \$ 46,200 |
| J-hook Vane (boulder) | EACH | 2 | \$ 1,300 | \$ 2,600 |
| J-hook Vane (log) | EACH | 4 | \$ 2,500 | \$ 10,000 |
| Log Vanes | EACH | 5 | \$ 1,750 | \$ 8,800 |
| Brush Mattress | SY | 150 | \$ 80 | \$ 12,000 |
| VRSS | SY | 240 | \$ 90 | \$ 21,600 |
| Coir Logs | LF | 110 | \$ 40 | \$ 4,400 |
| Plant Trees | EACH | 40 | \$ 300 | \$ 12,000 |
| Plant Shrubs | EACH | 520 | \$ 42 | \$ 21,900 |
| Plant Plugs | EACH | 520 | \$ 5 | \$ 2,600 |
| Seeding | ACRES | 3.5 | \$ 4,400 | \$ 15,400 |
| Coir Blanket | SY | 1930 | \$ 11 | \$ 21,300 |
| Live Stakes | EACH | 80 | \$ 6 | \$ 500 |
| Seeding and Erosion Control Blanket | SY | 100 | \$ 4 | \$ 400 |
| Annual Vegetation Maintenance | LS | 3 | \$ 6,708 | \$ 20,200 |
| Construction Total | | | | \$ 431,700 |
| Construction Total w/ Contingency (20%) | | | | \$ 518,000 |
| Planning, Engineering & Design (30%) | | | | \$ 155,400 |
| Construction Management (10%) | | | | \$ 51,800 |
| Project Total | | | | \$ 726,000 |
| Total w/ Construction Lower Bound (-20%), Legal, and Engineering | | | | \$ 581,000 |
| Total w/ Construction Upper Bound (+30%), Legal, and Engineering | | | | \$ 944,000 |
| Annual Maintenance Cost (2%) | | | | \$ 14,600 |

Cost Estimates

| | |
|--|----------------|
| High Priority Sites: 30-yr and Annualized Cost analysis | Project Total |
| Category: | Bioengineering |
| Estimated life span (years) | 20 |
| Number of major maint. Events | 1 |
| Annual maintenance % of original project cost | 15% |
| End of life span % of original project cost | 25% |
| Expected annual maintenance | \$ 5,600 |
| End of life span maintenance | \$ 181,500 |
| Future Capital Cost | \$ 1,762,200 |
| Future annual maintenance | \$ 266,420 |
| Future end of life span cost | \$ 327,810 |
| Total Future Worth | \$ 2,356,000 |
| Annualized Cost | \$ 50,000 |
| Annual Maintenance Cost | \$ 14,500 |

Cost Estimates

Plymouth Creek - Alternative 2, High and Medium Sites

| Item Description | Unit | Estimated Quantity | Unit Price | Extension |
|--|-------|--------------------|------------|--------------|
| Mobilization | LS | 1 | \$ 111,760 | \$ 111,800 |
| Control of Water | LS | 1 | \$ 60,000 | \$ 60,000 |
| Erosion Control | LS | 1 | \$ 47,635 | \$ 47,700 |
| Clearing and Grubbing | ACRE | 1.9 | \$ 21,500 | \$ 40,900 |
| Clear and Grub Woody Invasive Plant Removal (<=6" DBH tree) | ACRE | 10.5 | \$ 5,700 | \$ 59,900 |
| Clear and Grub Woody Invasive Plant Removal (>=6" DBH tree) | EACH | 18 | \$ 700 | \$ 12,600 |
| Herbaceous vegetation herbicide treatment | ACRE | 10.5 | \$ 1,000 | \$ 10,500 |
| Select Tree Removal (>6") | EACH | 371 | \$ 450 | \$ 167,000 |
| Debris Removal | EACH | 26 | \$ 1,450 | \$ 37,700 |
| Grading | SY | 8070 | \$ 3 | \$ 24,300 |
| Common Excavation | CY | 480 | \$ 16 | \$ 7,700 |
| Fieldstone Riprap | TONS | 670 | \$ 120 | \$ 80,400 |
| Clear and Salvage Trees and Install as Root Wad | EACH | 3 | \$ 700 | \$ 2,100 |
| Cross Vane | EACH | 20 | \$ 4,200 | \$ 84,000 |
| J-hook Vane (boulder) | EACH | 4 | \$ 1,300 | \$ 5,200 |
| J-hook Vane (log) | EACH | 11 | \$ 2,500 | \$ 27,500 |
| Log Vanes | EACH | 28 | \$ 1,750 | \$ 49,000 |
| Brush Mattress | SY | 360 | \$ 80 | \$ 28,800 |
| VRSS | SY | 410 | \$ 90 | \$ 36,900 |
| Coir Logs | LF | 550 | \$ 40 | \$ 22,000 |
| Plant Trees | EACH | 90 | \$ 300 | \$ 27,000 |
| Plant Shrubs | EACH | 2050 | \$ 42 | \$ 86,100 |
| Plant Plugs | EACH | 2050 | \$ 5 | \$ 10,300 |
| Seeding | ACRES | 10.9 | \$ 4,400 | \$ 48,000 |
| Coir Blanket | SY | 7350 | \$ 11 | \$ 80,900 |
| Live Stakes | EACH | 450 | \$ 6 | \$ 2,700 |
| Seeding and Erosion Control Blanket | SY | 300 | \$ 4 | \$ 1,200 |
| Annual Vegetation Maintenance | LS | 3 | \$ 19,054 | \$ 57,200 |
| Construction Total | | | | \$ 1,229,400 |
| Construction Total w/ Contingency (20%) | | | | \$ 1,475,300 |
| Planning, Engineering & Design (30%) | | | | \$ 442,600 |
| Construction Management (10%) | | | | \$ 147,500 |
| Project Total | | | | \$ 2,066,000 |
| Total w/ Construction Lower Bound (-20%), Legal, and Engineering | | | | \$ 1,653,000 |
| Total w/ Construction Upper Bound (+30%), Legal, and Engineering | | | | \$ 2,686,000 |
| Annual Maintenance Cost (2%) | | | | \$ 41,400 |

Cost Estimates

| | |
|---|----------------|
| High and Medium Priority Sites: 30-yr and Annualized Cost analysis | Project Total |
| Category: | Bioengineering |
| Estimated life span (years) | 20 |
| Number of major maint. Events | 1 |
| Annual maintenance % of original project cost | 15% |
| End of life span % of original project cost | 25% |
| Expected annual maintenance | \$ 19,700 |
| End of life span maintenance | \$ 516,500 |
| Future Capital Cost | \$ 5,014,700 |
| Future annual maintenance | \$ 937,240 |
| Future end of life span cost | \$ 932,860 |
| Total Future Worth | \$ 6,885,000 |
| Annualized Cost | \$ 145,000 |
| Annual Maintenance Cost | \$ 41,300 |

Cost Estimates

Plymouth Creek - Alternative 3, High, Medium and Low Sites

| Item Description | Unit | Estimated Quantity | Unit Price | Extension |
|--|-------|--------------------|------------|--------------|
| Mobilization | LS | 1 | \$ 118,780 | \$ 118,800 |
| Control of Water | LS | 1 | \$ 60,000 | \$ 60,000 |
| Erosion Control | LS | 1 | \$ 50,800 | \$ 50,800 |
| Clearing and Grubbing | ACRE | 2.3 | \$ 21,500 | \$ 49,500 |
| Clear and Grub Woody Invasive Plant Removal (<=6" DBH tree) | ACRE | 12.9 | \$ 5,700 | \$ 73,600 |
| Clear and Grub Woody Invasive Plant Removal (>=6" DBH tree) | EACH | 18 | \$ 700 | \$ 12,600 |
| Herbaceous vegetation herbicide treatment | ACRE | 12.9 | \$ 1,000 | \$ 12,900 |
| Select Tree Removal (>6") | EACH | 372 | \$ 450 | \$ 167,400 |
| Debris Removal | EACH | 26 | \$ 1,450 | \$ 37,700 |
| Grading | SY | 9290 | \$ 3 | \$ 27,900 |
| Common Excavation | CY | 1100 | \$ 16 | \$ 17,600 |
| Fieldstone Riprap | TONS | 670 | \$ 120 | \$ 80,400 |
| Clear and Salvage Trees and Install as Root Wad | EACH | 3 | \$ 700 | \$ 2,100 |
| Cross Vane | EACH | 20 | \$ 4,200 | \$ 84,000 |
| J-hook Vane (boulder) | EACH | 4 | \$ 1,300 | \$ 5,200 |
| J-hook Vane (log) | EACH | 11 | \$ 2,500 | \$ 27,500 |
| Log Vanes | EACH | 28 | \$ 1,750 | \$ 49,000 |
| Brush Mattress | SY | 360 | \$ 80 | \$ 28,800 |
| VRSS | SY | 410 | \$ 90 | \$ 36,900 |
| Coir Logs | LF | 550 | \$ 40 | \$ 22,000 |
| Plant Trees | EACH | 91 | \$ 300 | \$ 27,300 |
| Plant Shrubs | EACH | 2050 | \$ 42 | \$ 86,100 |
| Plant Plugs | EACH | 2050 | \$ 5 | \$ 10,300 |
| Seeding | ACRES | 13.3 | \$ 4,400 | \$ 58,600 |
| Coir Blanket | SY | 8570 | \$ 11 | \$ 94,300 |
| Live Stakes | EACH | 450 | \$ 6 | \$ 2,700 |
| Seeding and Erosion Control Blanket | SY | 400 | \$ 4 | \$ 1,600 |
| Annual Vegetation Maintenance | LS | 3 | \$ 20,320 | \$ 61,000 |
| Construction Total | | | | \$ 1,306,600 |
| Construction Total w/ Contingency (20%) | | | | \$ 1,567,900 |
| Planning, Engineering & Design (30%) | | | | \$ 470,400 |
| Construction Management (10%) | | | | \$ 156,800 |
| Project Total | | | | \$ 2,196,000 |
| Total w/ Construction Lower Bound (-20%), Legal, and Engineering | | | | \$ 1,757,000 |
| Total w/ Construction Upper Bound (+30%), Legal, and Engineering | | | | \$ 2,855,000 |
| Annual Maintenance Cost (2%) | | | | \$ 44,000 |

Cost Estimates

| | |
|--|----------------|
| High, Medium, and Low Priority Sites: 30-yr and Annualized Cost ana | Project Total |
| Category: | Bioengineering |
| Estimated life span (years) | 20 |
| Number of major maint. Events | 1 |
| Annual maintenance % of original project cost | 15% |
| End of life span % of original project cost | 25% |
| Expected annual maintenance | \$ 23,300 |
| End of life span maintenance | \$ 549,000 |
| Future Capital Cost | \$ 5,330,300 |
| Future annual maintenance | \$ 1,108,510 |
| Future end of life span cost | \$ 991,560 |
| Total Future Worth | \$ 7,430,000 |
| Annualized Cost | \$ 156,000 |
| Annual Maintenance Cost | \$ 43,900 |

Cost Estimates

Plymouth Creek - Sites 2d and 2e

| Item Description | Unit | Estimated Quantity | Unit Price | Extension |
|--|-------|--------------------|------------|------------|
| Mobilization | LS | 1 | \$ 18,860 | \$ 18,900 |
| Control of Water | LS | 1 | \$ 10,000 | \$ 10,000 |
| Erosion Control | LS | 1 | \$ 8,040 | \$ 8,100 |
| Clearing and Grubbing | ACRE | 0.6 | \$ 21,500 | \$ 12,900 |
| Clear and Grub Woody Invasive Plant Removal (<=6" DBH tree) | ACRE | 0 | \$ 5,700 | \$ - |
| Clear and Grub Woody Invasive Plant Removal (>=6" DBH tree) | EACH | 0 | \$ 700 | \$ - |
| Herbaceous vegetation herbicide treatment | ACRE | 0 | \$ 1,000 | \$ - |
| Select Tree Removal (>6") | EACH | 42 | \$ 450 | \$ 18,900 |
| Debris Removal | EACH | 18 | \$ 1,450 | \$ 26,100 |
| Grading | SY | 2460 | \$ 3 | \$ 7,400 |
| Common Excavation | CY | 0 | \$ 16 | \$ - |
| Fieldstone Riprap | TONS | 0 | \$ 120 | \$ - |
| Clear and Salvage Trees and Install as Root Wad | EACH | 2 | \$ 700 | \$ 1,400 |
| Cross Vane | EACH | 0 | \$ 4,200 | \$ - |
| J-hook Vane (boulder) | EACH | 0 | \$ 1,300 | \$ - |
| J-hook Vane (log) | EACH | 0 | \$ 2,500 | \$ - |
| Log Vanes | EACH | 10 | \$ 1,750 | \$ 17,500 |
| Brush Mattress | SY | 110 | \$ 80 | \$ 8,800 |
| VRSS | SY | 0 | \$ 90 | \$ - |
| Coir Logs | LF | 0 | \$ 40 | \$ - |
| Plant Trees | EACH | 17 | \$ 300 | \$ 5,100 |
| Plant Shrubs | EACH | 670 | \$ 42 | \$ 28,200 |
| Plant Plugs | EACH | 670 | \$ 5 | \$ 3,400 |
| Seeding | ACRES | 0.199972222 | \$ 4,400 | \$ 900 |
| Coir Blanket | SY | 2460 | \$ 11 | \$ 27,100 |
| Live Stakes | EACH | 50 | \$ 6 | \$ 300 |
| Seeding and Erosion Control Blanket | SY | 700 | \$ 4 | \$ 2,800 |
| Annual Vegetation Maintenance | LS | 3 | \$ 3,216 | \$ 9,700 |
| Construction Total | | | | \$ 207,500 |
| Construction Total w/ Contingency (20%) | | | | \$ 249,000 |
| Planning, Engineering & Design (30%) | | | | \$ 74,700 |
| Construction Management (10%) | | | | \$ 24,900 |
| Project Total | | | | \$ 349,000 |
| Total w/ Construction Lower Bound (-20%), Legal, and Engineering | | | | \$ 280,000 |
| Total w/ Construction Upper Bound (+30%), Legal, and Engineering | | | | \$ 454,000 |
| Annual Maintenance Cost (2%) | | | | \$ 7,000 |

Cost Estimates

| | |
|--|----------------|
| Sites 2d and 2e: 30-yr and Annualized Cost analysis | Project Total |
| Category: | Bioengineering |
| Estimated life span (years) | 20 |
| Number of major maint. Events | 1 |
| Annual maintenance % of original project cost | 15% |
| End of life span % of original project cost | 25% |
| Expected annual maintenance | \$ 4,200 |
| End of life span maintenance | \$ 87,250 |
| Future Capital Cost | \$ 847,100 |
| Future annual maintenance | \$ 199,820 |
| Future end of life span cost | \$ 157,580 |
| Total Future Worth | \$ 1,205,000 |
| Annualized Cost | \$ 25,000 |
| Annual Maintenance Cost | \$ 7,000 |

Cost Estimates

Plymouth Creek - Channel Re-Meander

| Item Description | Unit | Estimated Quantity | Unit Price | Extension |
|--|-------|--------------------|------------|------------|
| Mobilization | LS | 1 | \$ 34,780 | \$ 34,800 |
| Control of Water | LS | 1 | \$ 10,000 | \$ 10,000 |
| Erosion Control | LS | 1 | \$ 15,210 | \$ 15,300 |
| Clearing and Grubbing | ACRE | 1.744719927 | \$ 21,500 | \$ 37,600 |
| Clear and Grub Woody Invasive Plant Removal (<=6" DBH tree) | ACRE | 0 | \$ 5,700 | \$ - |
| Clear and Grub Woody Invasive Plant Removal (>=6" DBH tree) | EACH | 0 | \$ 700 | \$ - |
| Herbaceous vegetation herbicide treatment | ACRE | 0 | \$ 1,000 | \$ - |
| Select Tree Removal (>6") | Each | 10 | \$ 450 | \$ 4,500 |
| Debris Removal | LS | 0 | \$ - | \$ - |
| Grading | SY | 0 | \$ 3 | \$ - |
| Common Excavation and Refill Original Ditch | CY | 1600 | \$ 4 | \$ 6,400 |
| Common Excavation and Remove from Site | CY | 1500 | \$ 16 | \$ 24,000 |
| Fieldstone Riprap | SY | 0 | \$ 120 | \$ - |
| Clear and Salvage Trees and Install as Root Wad | EACH | 0 | \$ 700 | \$ - |
| Cross Vane | EACH | 0 | \$ 4,200 | \$ - |
| J-hook Vane (boulder) | EACH | 0 | \$ 1,300 | \$ - |
| J-hook Vane (log) | EACH | 0 | \$ 2,500 | \$ - |
| Log Vanes | EACH | 0 | \$ 1,750 | \$ - |
| Brush Mattress | SY | 0 | \$ 80 | \$ - |
| VRSS | SFF | 0 | \$ 90 | \$ - |
| Coir Logs | LF | 0 | \$ 40 | \$ - |
| Plant Trees | EACH | 5 | \$ 300 | \$ 1,500 |
| Plant Shrubs | EACH | 3650 | \$ 42 | \$ 153,300 |
| Plant Plugs | EACH | 3650 | \$ 5 | \$ 18,300 |
| Seeding | ACRES | 1.504820937 | \$ 4,400 | \$ 6,700 |
| Coir Blanket | SY | 2100 | \$ 11 | \$ 23,100 |
| Live Stakes | EACH | 0 | \$ 6 | \$ - |
| Seeding and Erosion Control Blanket | SY | 7200 | \$ 4 | \$ 28,800 |
| Annual Vegetation Maintenance | LS | 3 | \$ 6,084 | \$ 18,300 |
| Construction Total | | | | \$ 382,600 |
| Construction Total w/ Contingency (20%) | | | | \$ 459,100 |
| Planning, Engineering & Design (30%) | | | | \$ 137,700 |
| Construction Management (10%) | | | | \$ 45,900 |
| Project Total | | | | \$ 643,000 |
| Total w/ Construction Lower Bound (-20%), Legal, and Engineering | | | | \$ 515,000 |
| Total w/ Construction Upper Bound (+30%), Legal, and Engineering | | | | \$ 836,000 |
| Annual Maintenance Cost (2%) | | | | \$ 12,900 |

Cost Estimates

| | |
|---|----------------|
| Channel Re-Meander: 30-yr and Annualized Cost analysis | Project Total |
| Category: | Bioengineering |
| Estimated life span (years) | 20 |
| Number of major maint. Events | 1 |
| Annual maintenance % of original project cost | 15% |
| End of life span % of original project cost | 25% |
| Expected annual maintenance | \$ 4,500 |
| End of life span maintenance | \$ 160,750 |
| Future Capital Cost | \$ 1,560,700 |
| Future annual maintenance | \$ 214,090 |
| Future end of life span cost | \$ 290,330 |
| Total Future Worth | \$ 2,065,000 |
| Annualized Cost | \$ 43,000 |
| Annual Maintenance Cost | \$ 12,900 |